



Govt. Servants Co-operative House Building Society Ltd.

VASANT VIHAR CLUB

88, Paschimi Marg, Vasant Vihar, New Delhi-110057 Tel :+ 91 11 4070 1323

E-mail: generalmanagervvc@gmail.com acctvvc@gmail.com+ 91 11 4070 1324

GST No.: 07AAFAG0794D1ZU PAN No. AAFAG0794D

Website : www.vasantvihar.co

Ref. No.VVC/ADMN/EL/2006

27 July 2026

Sub: Invitation of Tender for Up gradation of Main L.T. Panel (Indoor Floor Mounted- Panel Room) in Vasant Vihar Club.

NOTICE INVITING SEALED QUOTATIONS

Sealed quotations, superscribed "Quotation for Up gradation Main L.T. Panel (Indoor, Floor Mounted – Panel Room)", are invited from experienced and eligible electrical contractors for the up gradation, testing, and commissioning of Main L.T. Panel as per the attached technical specifications and schedule of work.

The sealed quotations should reach the office of the **General Manager, Vasant Vihar Club, 88, Paschimi Marg, Vasant Vihar, New Delhi – 110057**, on or before **4:00 PM on 31.07.2026**.

The quotations shall be submitted strictly in accordance with the attached specifications, terms and conditions, and scope of work. Quotations received after the stipulated date and time shall not be considered.

1. Scope of Work

1. Main L.T. Panel (Indoor Floor Mounted - Panel Room) Qty. 01 Nos.			
S.No	Item Description	Make	Qty
A	M.S. ENCLOSURE: - POWDER COATED RAL – 7035		
1	2.0/1.6mm CRCA Sheet (Make: -TATA/Eq.) Enclosure IP42 (Indoor Floor Mounted Type) of Size: - 1875 H x 1750 W x 700 D mm approx....	Enclosure-E-FAB CRCA Sheet-TATA/Eq.	1
B	INCOMER - 1 : - Direct form Transformer		
2	1000A TP MCCB 36kA Thermal Magnetic OL SC Protection along with Spreader Links &Extended ROH	L&T	1
C	METERING &INDICATION: -		
3	Digital VAF (Volt, Amp. & Freq.) Meter CL1.0	Secure	1

4	Current Transformer CT - 1000/5A CL1.0	AE	3
5	6A SP control MCB	L&T/Siemens	3
6	RYB Phase Indication	Pecox	1 Set
D	OUTGOING: -		
7	630A TP MCCB 36kA Thermal Magnetic OL SC Protection along with Spreader Links &Extended ROH - For A.C. Panel	L&T	1
8	400A TP MCCB 36kA Thermal Magnetic OL SC Protection along with Spreader Links &Extended ROH - For Tennis Court Complex Panel	L&T	1
E	AL. BUS-BAR SECTION: -		
9	1200A ALU. BUSBAR	Jindal/Eq.	1 Lot
F	INCOMER - 2 : - Direct form AMF Panel		
10	800A TP MCCB 36kA Thermal Magnetic OL SC Protection along with Spreader Links &Extended ROH	L&T	1
G	METERING &INDICATION: -		
11	Digital VAF (Volt, Amp. & Freq.) Meter CL1.0	Secure	1
12	Current Transformer CT - 800/5A CL1.0	AE	3
13	6A SP control MCB	L&T/Siemens	3
14	RYB Phase Indication	Pecox	1 Set
H	OUTGOING: -		
15	630A TP MCCB 36kA Thermal Magnetic OL SC Protection along with Spreader Links &Extended ROH - For L.T. Panel	L&T	1
16	630A TP MCCB 36kA Thermal Magnetic OL SC Protection along with Spreader Links &Extended ROH - For APFC (Power Factor) Panel	L&T	1
I	AL. BUS-BAR SECTION: -		
17	1000A ALU. BUSBAR	Jindal/Eq.	1 Lot
J	OTHER'S: -		
18	Panel Accessories (Hardware's, Terminal Blocks, Panel Locks, Gasket, Hinges, Thimbles, Wires, Earthing Strip / Stud etc.)	E-FAB/Reputed	1
19	Assembling & Wiring	E-FAB	1
20	Packing with Poly wrap	E-FAB	1

2. Terms & Conditions

1. The contractor shall visit the site and thoroughly inspect the nature and extent of the work before submitting the quotation. No claim arising out of lack of site inspection shall be entertained later.
2. If any additional repair or allied work is observed during the site inspection, the contractor shall quote the rates for such work separately.
3. The entire work shall be completed within **10 (Ten) days** from the date of issuance of the Work Order.
4. Upon completion of the work, the contractor shall remove all debris, unused materials, and waste, and hand over the site in a neat and clean condition.
5. An advance payment of **30%** of the work order value shall be released for mobilization of the work.
6. A further **50%** payment shall be released after the successful fabrication, delivery, installation, and satisfactory inspection of the materials by the Club's Electrical Engineer/Electrician or authorized representative.
7. **10%** of the work order value shall be released after successful testing and commissioning of the Main L.T. Panel.
8. The remaining **10%** shall be retained as **Retention Money** and shall be released after **three (03) months** from the date of successful commissioning, subject to satisfactory performance of the panel and rectification of any defects noticed during the defect liability period.
9. The contractor shall submit self-attested copies of the **PAN Card, GST Registration Certificate** (or other applicable tax registration), and any other statutory documents required by the Club.
10. **Tax Deducted at Source (TDS)** shall be deducted from the contractor's bills as per the provisions of the Income Tax Act and other applicable statutory regulations.
11. The contractor shall adhere strictly to the stipulated completion period. In case of delay attributable to the contractor, a penalty of **Rs. 500/- (Rupees Five Hundred only) per day** shall be levied for each day of delay, unless an extension of time is granted in writing by the competent authority.


Rajan Kapoor
General Manager
Vasant Vihar Club